

Published in Bulletin 42
HRB 1951

REPORT ON THE
FOUNDATION ROLLING
BRANDYWINE ARTERIAL EXTENSION (ROUTE 7)
CITY OF BINGHAMTON, NEW YORK

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
BUREAU OF SOIL MECHANICS

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

REPORT ON THE
FOUNDATION ROLLING
BRANDYWINE ARTERIAL EXTENSION (ROUTE 7)
CITY OF BINGHAMTON, NEW YORK

ALBANY, NEW YORK

DECEMBER 1949

STATE OF NEW YORK
IN SENATE
JANUARY 1, 1902
REPORT OF THE
COMMISSIONER OF THE
LAND OFFICE

REPORT OF THE
COMMISSIONER OF THE
LAND OFFICE
(IN RESPONSE TO RESOLUTION
OF THE SENATE, PASSED
MAY 1, 1901)

TABLE OF CONTENTS

	<u>Page</u>
Introduction	1
Description of Site	2
Construction Methods Considered	5
Scope of Investigation	7
Equipment Used	9
Test Procedures	11
Test Results	14
Summary	21
Recommendations	24
Recommended Tentative Specifications	29
Acknowledgments	32
Appendix A	
Appendix B	
Appendix C	
Appendix D	

TABLE OF CONTENTS

1	Introduction
2	Description of Site
3	Construction Methods Compared
4	Scope of Investigation
5	Equipment Used
6	Test Procedures
7	Test Results
8	Summary
9	Recommendations
10	Recommended Tentative Specifications
11	References
12	Appendix A
13	Appendix B
14	Appendix C
15	Appendix D

FOUNDATION ROLLING
BRANDYWINE ARTERIAL EXTENSION (ROUTE 7)
CITY OF BINGHAMTON, NEW YORK

INTRODUCTION

This report presents the information obtained from a field investigation of the effectiveness of a heavy pneumatic tired roller in compacting a loose refuse fill by surface rolling.

This investigation was conducted at the site of the proposed Brandywine Arterial Extension (Route 7) in the City of Binghamton, New York. The present foundation between Stations 51+00 and 96+00 of this project consists of a city dump fill, varying in age from approximately 1 to 15 years, and extending to a depth variable from 5 to 25 feet.

The tests were undertaken to verify the belief that the upper layer of such a heterogeneous, loose fill could be compacted sufficiently by heavy surface rolling to eliminate local weak spots, and to give a uniform bearing value capable of supporting the intended fill embankments without distortion. The data obtained were necessary to determine the feasibility of this procedure of field construction, to prepare estimates of quantities, and to formulate specifications covering the work.

NYS
Library
50 Wolf Road, POD 34
Albany, New York 12232

DESCRIPTION OF SITE

The dump fill site within the limits of the Brandywine Arterial Extension extends approximately from Station 51/00 to Station 96/00. The fill is made up of the usual material found in such dump areas; including food refuse, paper and wood, glass, metals - such as tin cans and bed springs, ashes, and other miscellaneous matter, such as rubber tires and rags. The various percentages of these materials vary widely with depth and in horizontal directions, depending upon the season of the year and the rate of dumping. Following the usual practices of land fill construction, a light cover of earth blankets the entire fill, which was placed with no specific effort to obtain compaction. The area consequently is a random, irregular fill, with wide variations in density and load carrying capacities. No record is available of the ages of the sections of this fill.

Prior to the construction of the dump fill this area was the location of a meandering creek in low flat lands, and consequently, the material underlying the fill consists of unconsolidated muck, silt, and clay. In some locations scattered pockets of mixtures of fine sand, gravel, and silt, are found at varying depths below the original ground surface. Figures A-11 and A-12 of Appendix A show the depth of the dump fill and the underlying soil profile within this area.

DESCRIPTION OF SITE

The same fill also exists on the sides of the

excavation (see sketch) and extends to the west of the
excavation (see sketch) to station 15+00. The fill is made
up of the usual material found in such areas:

including rock, gravel, sand, silt, clay, etc.

such as tin cans and old bottles, etc., and other

miscellaneous matter, such as pieces of wood and iron.

The various fragments of these materials are very widely

distributed and in particular the fragments of broken glass

are common in the soil and the walls of the excavation.

The usual material of local fill construction, a

light cover of earth beneath the surface fill, which

was placed with no specific effort to obtain connection.

The area immediately in a trench, however, fill, with

the variations in density and local irregular connections.

No record is available of the use of the section of

this fill.

Refer to the construction of the same fill

the area was the location of a mountainous area in

the first lands, and consequently, the material was

light the fill consists of unconsolidated sand, silt,

and clay. In some locations scattered pieces of

pieces of tin cans, wood, and other, and found at

various depths below the surface of the ground.

The same fill and the material well mixed with

the same.

A review of the existing literature on the characteristics of land dump fills indicates that the settlement expected in such fills is due to two separate factors. The first of these is the settlement due to physical factors and mechanical adjustments and accounts for the major portion of the settlement.

This physical settlement can be subdivided into two components. The first component is the settlement due to the weight of the fill itself. This value has been measured to be approximately 30 percent of the height of fill, with 20 percent taking place during the first 6 months, and the remaining 10 percent during the following 18 months. The fill generally reaches stability under its own weight in approximately 2 years. The second component of the physical settlement is that which takes place due to a superimposed load on the fill, such as a highway fill or a structure. This settlement will continue for a period following construction, with the actual amount and rate being a function of the nature of the local fill material and the superimposed load.

The second factor contributing to settlement is that due to the decomposition of the refuse material in the fill. The amount of this settlement is relatively small, compared to the physical settlement, but it continues to take place for 30 or more years. However, experience has shown that, because of the minor value of this settlement, it is not necessary to wait until

1. The first part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

2. The second part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

3. The third part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

4. The fourth part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

5. The fifth part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

6. The sixth part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

7. The seventh part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the structure of the atom is determined by the laws of quantum mechanics.

ultimate stability is reached before proceeding with the use of the filled area.

CONSTRUCTION METHODS CONSIDERED

At a meeting held on February 15, 1949, at the Department of Public Works District Office in Binghamton, New York, which was attended by Messrs. F.W. Donovan, H.W. Morss, L.W. Swank, and M.N. Sinacori, the various possible methods of construction were discussed. Among these were the following:

1. Removal of the unsuitable material by excavation and backfilling with acceptable borrow. This method was considered very expensive and impractical due to: (a) the large quantities involved; (b) the problem of finding a suitable waste area well beyond the city limits, and its consequent long haul; and, (c) the sanitary precautions necessary for handling the material at the site and through the city streets.
2. Building the fill on the foundation in its present state, without any excavation, and untreated in any manner. It was felt that this procedure would result in a pavement reflecting considerable unevenness and local differential settlement, and which would require large expenditures for maintenance after construction. In addition, the pavement would generally be rough riding and dangerous.
3. Stabilizing the foundation by the injection of chemicals or grouting materials. This method was

THE UNIVERSITY OF CHICAGO

REPORT OF THE

COMMISSIONER OF THE

BOARD OF EDUCATION

FOR THE YEAR

1900-1901

CHICAGO, ILL.

1901

PRINTED BY THE

UNIVERSITY OF CHICAGO PRESS

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

THE UNIVERSITY OF CHICAGO

CHICAGO, ILL.

1901

considered to be uncertain and expensive due to the large number of close-spaced holes required for adequate coverage.

4. Compacting the foundation in place to a greater density and a higher bearing value to the maximum obtainable depth, by a heavy impact or rolling load. Of these it was felt that a heavy rolling load would be the more practical and economical, and was the method developed and covered in this investigation.

1. The first part of the paper is devoted to a discussion of the general principles of the theory of the structure of the atom. It is shown that the structure of the atom is determined by the laws of quantum mechanics, and that the laws of quantum mechanics are based on the principle of the uncertainty of the position and momentum of the particles.

2. In the second part of the paper, the author discusses the problem of the structure of the nucleus. It is shown that the structure of the nucleus is determined by the laws of quantum mechanics, and that the laws of quantum mechanics are based on the principle of the uncertainty of the position and momentum of the particles. The author also discusses the problem of the structure of the nucleon, and shows that the structure of the nucleon is determined by the laws of quantum mechanics, and that the laws of quantum mechanics are based on the principle of the uncertainty of the position and momentum of the particles.

SCOPE OF INVESTIGATION

Preparations for the investigation were predicated on the belief that a heavy pneumatic tired roller rolled over the area a sufficient number of times would compact the upper portion of the dump fill to furnish a satisfactory bearing value, and designate the local weak spots, which might be treated separately. It was felt that this method would develop a compacted crust several feet in thickness as the upper layer of the foundation dump fill, pre-consolidated by the rolling to reduce the settlement expected due to the superimposed fill load. On this would be added several additional feet of well compacted fill. The combination of these would support a flexible pavement sufficiently to eliminate abrupt differential settlements, and minimize the gradual settlement covering long stretches.

To determine the feasibility of such a method, and to obtain specific information with which to prepare the necessary plans and specifications, field data was required to cover the following points:

1. The effective weight or weights of roller needed to compact the foundation to a satisfactory density.
2. The order of increasing the roller weight to obtain satisfactory rolling without causing too much lateral displacement, or deep ruts that would interfere with

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

1911

the rolling operations.

3. The number of roller passes required.
4. The effect of these operations on the dump fill areas of different ages.
5. The depths to which the rolling was effective in contributing to a compacted crust.

EQUIPMENT USED

Before the investigation was started, some thought was given to the possible type and weight of equipment which could be used to meet the developed requirements. At this time, the William Bros Boiler and Manufacturing Company of Minneapolis, Minnesota, offered the use of their new 50-Ton Compactor, recently put on the market by them. It was therefore decided to use this Bros roller for the investigation, as it was felt that it met the requirements.

The roller consists of a large metal box approximately 17 feet long by 8 feet wide, under which are centered two axles in line, each with two rubber tires of size 18:00 x 24-24 ply. A tongue neck extends from the box to two front dolly wheels, and a tie-bar connects the dolly wheels to the tractor. The empty weight of the roller is 12 tons, and the box is of such capacity that it can be loaded with saturated sand to a total weight of 50 tons. For this experiment, the roller was used at three different weights: empty weighing 12 tons, loaded to half load at 31 tons, and finally loaded to full capacity at a total weight of 50 tons.

During the tests, the roller was pulled first by a D-7 Caterpillar Tractor furnished by the Bero Engineering and Construction Company, and later by an HD-19 Allis-Chalmers Tractor furnished by the McDougall

Equipment Company of Binghamton, New York. The equipment used was furnished by these organizations at no cost to the State, but as a contribution to the development of the experiment.

TEST PROCEDURES

For the investigation, seven test strips were laid in various locations on the dump fill in such a manner that fills of different ages and composition would be included. Each test strip was 200 feet long and 20 feet wide. The locations of these test strips are shown in Figure A-11. After they were laid out, these test strips were cross-sectioned and referenced to established bench marks. During the rolling, additional cross-sections and profiles were taken periodically in every test strip to measure the amount of settlement or displacement taking place as a function of the number of roller passes and the weight of roller used.

In the first five test strips, the compaction tests were made in three separate stages. The first stage consisted of rolling the area with 12 full passes of the empty roller, which weighed 12 tons. In the second stage, the roller was loaded to a total weight of 31 tons, and the areas were rolled 12 additional times. Finally with the roller loaded to its capacity of 50 tons, the rolling was continued until no measurable settlement was noticed in these test strips. During these operations, local weak spots developed, into which the roller sank as much as 4 feet. These areas were backfilled and leveled off with a thin layer of sand and gravel before the rolling was continued.

The last two test strips were compacted only with the roller loaded to a total weight of 50 tons. It was thought advisable to compare the behavior of the roller fully loaded on material not previously compacted, to that on material previously compacted by light rolling, and to notice the number and depths of local depressions by a comparison of the two methods.

Attempts were made to measure the effects of rolling on the density of the dump fill material in place and on the depth to which the rolling was effective. The taking of samples to measure natural densities in place was not practicable because of the nature of the material. Two other methods, however, were used to obtain a measure of the relative change in density with depth. The first of these was the use of the electrical resistivity apparatus. The second method was the use of probing rods driven into the ground under standard conditions, and recording the number of blows for each foot of penetration.

Electrical Resistivity:-The use of the electrical resistivity apparatus in itself was an experiment, insofar as this method had not been used before for such work. The apparatus measures the resistance of an electrical current flowing through the soil material. It is known that the resistance of a material is lessened with an increase in the density of that material. The depth at which the resistance is being measured is

1. The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the transparency and accountability of the organization. This section also outlines the various methods used to collect and analyze data, ensuring that the information is reliable and up-to-date.

2. The second part of the document focuses on the financial aspects of the organization. It provides a detailed overview of the budget, including the projected income and expenses for the upcoming year. This section also discusses the various financial risks and how they are being managed to ensure the organization's financial stability.

3. The third part of the document addresses the operational aspects of the organization. It describes the various processes and procedures that are in place to ensure the efficient and effective delivery of services. This section also discusses the various challenges that the organization is facing and how they are being addressed.

4. The fourth part of the document discusses the human resources of the organization. It provides a detailed overview of the current staff levels and the various roles and responsibilities of the different departments. This section also discusses the various training and development programs that are in place to ensure that the staff is equipped with the necessary skills and knowledge to perform their duties effectively.

5. The fifth part of the document discusses the legal and regulatory aspects of the organization. It provides a detailed overview of the various laws and regulations that the organization is subject to and how they are being complied with. This section also discusses the various legal risks and how they are being managed to ensure the organization's legal compliance.

6. The sixth part of the document discusses the environmental aspects of the organization. It provides a detailed overview of the various environmental risks and how they are being managed to ensure the organization's environmental sustainability. This section also discusses the various environmental programs that are in place to reduce the organization's carbon footprint and promote sustainable practices.

7. The seventh part of the document discusses the social aspects of the organization. It provides a detailed overview of the various social risks and how they are being managed to ensure the organization's social responsibility. This section also discusses the various social programs that are in place to support the community and promote social development.

8. The eighth part of the document discusses the overall performance of the organization. It provides a detailed overview of the various key performance indicators (KPIs) that are used to measure the organization's performance and how they are being tracked. This section also discusses the various strategies that are in place to improve the organization's performance and achieve its goals.

9. The ninth part of the document discusses the future of the organization. It provides a detailed overview of the various opportunities and challenges that the organization is facing and how they are being addressed. This section also discusses the various strategies that are in place to ensure the organization's long-term success and sustainability.

10. The tenth part of the document discusses the conclusion of the report. It summarizes the key findings of the report and provides a final overview of the organization's performance and future prospects. This section also discusses the various recommendations that are being made to improve the organization's performance and achieve its goals.

dependent chiefly on the spacing of the electrodes on the ground. Two types of tests were used: The first is known as the point test, in which the electrode spacing, which controls the depth to which measurable effects are produced, was changed progressively from 1 to 20 feet. The second type of resistivity test made was the traverse test, in which the electrode interval is maintained constant and is progressed from one end of the line to the other. The point test gives a picture of changing resistance with depth, while the traverse test indicates the horizontal changes at a uniform depth. The results of these tests have been computed and plotted, and are included in Appendix C.

Probing Rods:-The relative increase in density due to rolling, measured by the use of probing rods, was done by driving into the ground 1-5/8 inch diameter rods with a 250 lb. hammer, dropped through a height of 6 inches. The number of blows required to drive the rods for each foot of depth was recorded. The variation in the number of blows was considered a relative measure of the change in density of the material. The probing rods were driven at various locations to include the portions of the fill which had not been rolled, and also others which had been given complete rolling coverage. By comparing the results of these two areas, the increase in resistance to penetration was attributed to an increase in density due to the surface rolling operations. The results of these tests are given in Appendix D.

1. The first part of the paper discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the success of any business or organization. The author argues that without reliable records, it is impossible to make informed decisions or to identify areas for improvement.

2. The second part of the paper focuses on the challenges of record-keeping in a digital age. While technology offers many advantages, it also introduces new risks, such as data loss and security breaches. The author suggests that organizations should implement robust backup and security protocols to mitigate these risks.

3. The third part of the paper explores the role of record-keeping in legal and regulatory compliance. It highlights the importance of maintaining records that can be used to demonstrate adherence to various laws and regulations. The author notes that failure to do so can result in significant penalties and legal consequences.

4. The fourth part of the paper discusses the importance of record-keeping in financial management. It explains how accurate records are necessary for preparing financial statements and for budgeting. The author argues that good record-keeping practices can help organizations identify trends and make more effective use of their resources.

5. The fifth part of the paper focuses on the importance of record-keeping in human resources management. It explains how records of employee performance, attendance, and training are essential for making fair and effective personnel decisions. The author suggests that organizations should develop clear policies and procedures for maintaining these records.

6. The sixth part of the paper discusses the importance of record-keeping in marketing and sales. It explains how records of customer interactions and sales performance are necessary for developing effective marketing strategies. The author argues that good record-keeping can help organizations understand their customers better and tailor their offerings to meet their needs.

7. The seventh part of the paper discusses the importance of record-keeping in research and development. It explains how records of experiments, observations, and findings are essential for advancing knowledge and innovation. The author argues that good record-keeping can help researchers track progress and identify areas for further investigation.

8. The eighth part of the paper discusses the importance of record-keeping in environmental management. It explains how records of environmental data and activities are necessary for monitoring and improving environmental performance. The author suggests that organizations should develop comprehensive systems for collecting and analyzing this data.

9. The ninth part of the paper discusses the importance of record-keeping in public administration. It explains how records of government activities and decisions are essential for ensuring transparency and accountability. The author argues that good record-keeping can help citizens understand how their government operates and hold it accountable for its actions.

10. The tenth part of the paper discusses the importance of record-keeping in the arts and humanities. It explains how records of creative works and cultural heritage are essential for preserving and promoting these fields. The author argues that good record-keeping can help ensure that the achievements of past generations are not lost and can be shared with future generations.

TEST RESULTS

The test results obtained during the investigation were computed, analyzed, and plotted in several ways to show the required relationships. Each test strip included 6 control sections across which profiles were taken at 2-foot intervals within the compacted width of 20 feet. The 6 control sections were laid out for each test strip as shown in Figure B-1 for Test Strip No. 3.

Profiles across these control sections were taken periodically during the rolling operations and were correlated with the number of passes and the various weights of roller used. Centerline profiles and additional sections at some of the weakest locations between these standard sections were taken as the investigation developed. To maintain control during the rolling operations, the average settlement across each of the 6 control sections for each test strip was plotted directly in the field against the number of passes given.

In the rolling operations, one pass was taken to represent two trips of the roller, each trip offset from the other the width of the one tire to obtain complete area coverage.

Figures B-2 to B-6 show the resulting average settlement obtained across each control section, plotted versus the number of roller passes given for the corresponding weights of roller. These plots show that the

12-ton roller gave an average settlement of 0.3 feet after 12 passes. The major portion of this settlement developed during the first 4 to 6 passes. The 12 additional passes of the 31-ton roller gave from 0.6 to 0.7 feet of additional settlement, for an average total of approximately 1 foot. The major portion of the settlement developed with the 31-ton roller was obtained during the first 8 passes. The 50-ton roller further increased the settlement to an average of 2 feet. The major portion of this settlement was realized during the first 20 to 25 passes of the roller. Further rolling with the 50-ton roller resulted in additional settlement, but the actual amount was relatively small.

Figures B-7 and B-8 show the settlement data plotted for Test Strip Nos. 6 and 7. In these two strips only the 50-ton roller was used, without prior rolling with a lighter weight roller. In Test Strip No. 6 a maximum of 2 feet of settlement was obtained in approximately 25 to 30 passes, at which time relative stability was obtained. Test Strip No. 7 showed approximately 1.7 feet of settlement during the first 5 passes of the 50-ton roller. The test on this strip was discontinued due to the very bad rutting that developed in some locations. This appeared to be one of the weaker strips tested, and would have given considerably more settlement if the test had been continued until stability was obtained.

1. The first part of the paper discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the success of any business or organization. The author argues that without reliable records, it is impossible to make informed decisions or to identify areas for improvement.

2. The second part of the paper focuses on the challenges of record-keeping in a digital age. While technology offers many advantages, it also introduces new risks, such as data loss and security breaches. The author suggests that organizations should implement robust backup and security protocols to mitigate these risks.

3. The third part of the paper explores the role of record-keeping in legal and regulatory compliance. It highlights the importance of maintaining records that can be used to demonstrate adherence to various laws and regulations. The author notes that failure to do so can result in significant penalties and legal consequences.

4. The fourth part of the paper discusses the importance of record-keeping in financial management. It explains how accurate records are necessary for calculating taxes, preparing financial statements, and monitoring the overall financial health of the organization. The author stresses that good record-keeping practices can help organizations avoid costly mistakes and optimize their financial performance.

5. The fifth part of the paper addresses the issue of record-keeping in human resources management. It discusses the need to maintain accurate records of employee information, including hiring, training, and performance. The author argues that these records are crucial for ensuring fair and equitable treatment of all employees and for resolving any disputes that may arise.

6. The sixth part of the paper concludes by summarizing the key points discussed and emphasizing the overall importance of record-keeping. The author reiterates that maintaining accurate and reliable records is not just a bureaucratic requirement, but a fundamental practice that underpins the success and sustainability of any organization.

The relationship between the average and maximum settlements is shown plotted in Figures B-9 and B-11 for several of the test sections recorded. On the average, the maximum local settlement within each test section was approximately 50 percent greater than the average settlement, with some sections showing as much as 100 percent variation.

The data was also plotted to show the cross sectional profile of the surface at each control section. These profiles are shown plotted in Figures B-12 to B-47, and are referenced with the number of passes required to give the developed profiles. On the average, the greatest settlement shown plotted on these sections was approximately 3-1/2 feet. In some of the locations between these control sections, settlement up to 4 feet was recorded.

It should be pointed out that there is considerable variation in the amount of settlement obtained, even across the narrow 20-foot width of the sections measured. In general, all of these sections show a greater settlement along the center of the test strip than toward the outside edges. This variation may have been due to the overlapping effects of the rolling, since one coverage over the full width of the test strip was composed of two passes, one pass covering each side of the centerline. The recorded differential settlement in some sections was as much as 3 feet.

Several of the centerline profiles developed during the investigation are shown plotted in Figure B-48. These accentuate the variability of the material within each test strip.

Electrical Resistivity:-The results of the electrical resistivity tests are shown plotted in Appendix C in two groups of curves. The first group, plotted in Figures C-1 to C-11, give the results of the point tests, which show the change of resistance with depth at one location. The second group, plotted in Figures C-12 to C-18, give the results of the traverse tests, which indicate the horizontal changes in resistance at a uniform depth. It should be pointed out that the results of this portion of the investigation are only qualitative, insofar as the relationship between the values of the resistance of the material to the passage of an electrical current and the corresponding density is unknown at this time. In general, the resistivity work was performed at the same locations within the test strips before and following each rolling operation. However, due to the lapse of time between these groups of tests, other variables may have come into being, such as rainfall which occurred during that period and which affected the resistance of the material.

Because of the local conditions, the effects of the decreased resistance were felt within the areas at varying depths up to 14 to 18 feet. However, analyzing

the data with allowances for these local variations, the point tests (Figures C-1 to C-11) show that rolling with the 12-ton roller was effective to an average depth of approximately 4 feet. Rolling with the 31-ton roller was effective to an average depth of approximately 6 feet, and rolling with a 50-ton roller was effective to an average depth of approximately 8 to 9 feet.

Except for local variations, the traverse test results (Figures C-12 to C-18) show that the measured resistance of the fill material showed a decrease in value to a depth of 10 feet, as the result of rolling. Where a traverse was made following rolling with the 12 and 31-ton roller and again following rolling with the 50-ton roller, the rolling with the 50-ton roller resulted in a further decrease in the resistance when compared to the values following the rolling with the 31-ton roller. The resistance obtained has been assumed as representing inversely a measure of the density of the material.

Probing Rods:-The results obtained from the use of probing rods to measure the relative increase in density due to rolling are given in Appendix D. The values of resistance to penetration as a function of the depth below the surface were averaged for the points within each test strip, to obtain a more representative relationship. These average values are shown plotted

in Figures D-1 to D-5. The individual results are included in table form in Figures D-6 to D-10.

All the work done with probing rods was undertaken after the rolling operations were completed. Consequently, in order to correlate the effects of rolling on the density as measured by the increased resistance to penetration of the rods, two groups of holes were driven in the area tested. The first group of holes was located adjacent to the test strips on material that had not been rolled, and represents the area before rolling. The second group was located along the same stations, but within the rolled test strips, and represents the area after it was rolled. This difference in locations introduced additional variables due to the heterogeneous nature of the material, which were evident in the test results. However, an analysis of the test data showed that the number of blows required to drive the probing rods into the ground in the rolled test strips was generally greater than those driven outside of the rolled test strips. The variation in the number of blows required to drive the probing rods for the first 10 feet has been averaged and is shown in the following summary.

	<u>In areas not rolled</u>	<u>In areas completely rolled</u>
Cumulated number of blows to drive probing rods from 0 to 5 feet..	65	130
Average number of blows per foot to drive rods from 0 to 5 feet.	13	26
Cumulated number of blows to drive probing rods from 5 to 10 feet.	45	73
Average number of blows per foot to drive rods from 5 to 10 feet.	9	15

The curves generally show that an increase in resistance to penetration has been realized to a depth of approximately 8 feet. The number of blows required to drive the rods through the top 5 feet in the areas completely rolled was approximately double the corresponding number of blows in the areas not rolled. Beyond a depth of 10 feet, the variations obtained are only within the limits of error assumed.

SUMMARY

The following summary has been obtained from the details of the investigation:

1. The dump fill within the limits of the Brandywine Arterial Extension can be pre-consolidated by rolling with a heavy pneumatic tired roller. This rolling should develop a compacted crust sufficiently thick to offer relatively uniform support to a light fill and permit the construction of a serviceable flexible pavement.
2. The settlement obtained in the foundation due to rolling with the empty roller weighing 12 tons was relatively small. This value averaged approximately 0.3 feet over the entire area. It is felt that the 12-ton roller is too light for effective rolling, and should not be used during construction.
3. Rolling the foundation directly with the roller fully loaded to 50 tons without prior rolling with a lighter roller developed many deep ruts and holes with the first few roller passes. In addition to tearing and loosening the material, this method slowed down operations considerably, insofar as too much time was spent in pulling the roller out of these depressions. The 30-ton roller, however, did not cause too much difficulty in this respect.

4. The data shows that the bulk of the settlement due to the 30-ton roller was realized within the first 6 to 8 passes. The few additional passes increased the amount of settlement very little.
5. Using the 50-ton roller, the major portion of the settlement was obtained in approximately 20 to 25 passes. Additional minor settlement was obtained with further rolling.
6. Observations made during the testing program indicated that there is no practical means of setting up standards or procedures in the field to measure the settlement or required stability, without interfering with the construction schedule.
7. The rolling operations proceeded most smoothly when all ruts and local depressions which developed during rolling were backfilled with granular material. It was observed during the investigation, however, that if too thick a layer of sand and gravel were spread, it reduced the effectiveness of rolling and prevented additional settlement.
8. During the investigation, there were no local weak spots encountered which could not be strengthened by backfilling and re-rolling as described in the

report. Although there may be such locations in the area, no special provisions need be made for the removal of any material by excavation.

9. The electrical resistivity apparatus showed that rolling with the 30-ton roller was felt to a depth of approximately 6 feet, and that rolling with the 50-ton roller was felt to a depth of 8 to 9 feet. The results of the rod probings showed an increase in resistance to driving to an average depth of 8 feet. There were some areas which showed no change in resistance, while others showed change to a greater depth. Although it is not known what the direct relationship is between the change in resistance to the flow of an electric current and the change in density, nor the relationship between the number of blows on the rods and the density, it has been concluded that a crust has been formed on the surface of the dump fill which has a greater density and bearing value than before rolling, and which is affected to a depth of at least 5 feet.
10. The results of the investigation show that an average area settlement of 2 to 2-1/2 feet may be expected due to the foundation rolling.

RECOMMENDATIONS

From the results of the investigation, the following recommendations are made to aid in the detailed design and the preparation of specifications for the portion of the Brandywine Arterial Extension between Stations 51 and 96.

1. The rolling operations throughout the area be carried on in two stages. The first stage should include complete coverage with the roller weighing from 25 to 30 tons. The second stage rolling should then follow using the roller weighing a total of 50 tons. The rolling should cover the area from toe to toe of slope.
2. The preliminary or first stage rolling be set up to include 8 passes of the 30-ton roller throughout the area. The second stage rolling should be estimated on the basis of 30 additional passes of the 50-ton roller. On the basis of these 38 passes of the roller at an average speed of 2 miles per hour, there will be required approximately 400 rolling hours for the foundation rolling operations. It is recommended that this value be rounded to 500 rolling hours for estimating purposes.
3. The tentative unit price of the rolling operation, exclusive of the cost of the roller, has been

REPORT

The first part of the report deals with the general situation of the country. It is a very interesting and informative study of the country's history and its present state. The author has done a great deal of research and has gathered a wealth of material. The report is well written and is a valuable contribution to the study of the country.

The second part of the report deals with the economic situation of the country. It is a very interesting and informative study of the country's economy and its present state. The author has done a great deal of research and has gathered a wealth of material. The report is well written and is a valuable contribution to the study of the country's economy.

The third part of the report deals with the social situation of the country. It is a very interesting and informative study of the country's society and its present state. The author has done a great deal of research and has gathered a wealth of material. The report is well written and is a valuable contribution to the study of the country's society.

The fourth part of the report deals with the political situation of the country. It is a very interesting and informative study of the country's politics and its present state. The author has done a great deal of research and has gathered a wealth of material. The report is well written and is a valuable contribution to the study of the country's politics.

estimated approximately at \$25.00 per hour, as follows:

D-8 Tractor and Operator	\$7.00 per hr.
D-8 Bulldozer and Operator	8.00 per hr.
Fuel, maintenance, insurance, profits, etc.	<u>10.00 per hr.</u>
	\$25.00 per hr.

The unit price of the roller, based on a prorated rental rate of \$1000.00 per month, would be approximately \$5.00 per hour. However, if the cost of the roller were charged off to this project, its unit price would be \$25.00 per hour, based on a cost of \$12,500.00, and 500 rolling hours. The total unit price for the complete operation would then be either (a) \$30.00 per hour, or (b) \$50.00 per hour. The corresponding total estimated price for the foundation rolling would be either (a) \$15,000.00, or (b) \$25,000.00, exclusive of the price of Item 2EC. The actual unit price bid probably will be dependent on the availability of the roller, and on its anticipated future use. Additional information is required to arrive at a more reasonable estimate.

4. The depressions developed in the foundation during rolling operations should be backfilled with selected borrow, Item 2EC. The quantity should be the minimum required to level off the area and permit continued easy rolling. It is estimated

1. The first part of the paper is devoted to a general discussion of the problem of the origin of life.

2. The second part of the paper is devoted to a detailed discussion of the problem of the origin of life.

3. The third part of the paper is devoted to a detailed discussion of the problem of the origin of life.

4. The fourth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

5. The fifth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

6. The sixth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

7. The seventh part of the paper is devoted to a detailed discussion of the problem of the origin of life.

8. The eighth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

9. The ninth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

10. The tenth part of the paper is devoted to a detailed discussion of the problem of the origin of life.

that there may be needed approximately 12 inches of selected borrow over the entire area, with the actual quantity at any location varying with local conditions. On this basis, there will be needed approximately 20,000 cubic yards for the area between Stations 51 and 96. It is recommended that 20,000 cubic yards of Item 2EC be provided for this portion of the project. A note should be added to the plans explaining that the minimum amount of Item 2EC required for ease of rolling will be used, and that, depending upon local conditions during construction, only a portion of it may actually be used.

5. Since it is not practical to set up a field procedure to measure the settlement during rolling, it is recommended that the Engineer on the project decide by visual and measured observations when sufficient rolling has been obtained.
6. The rolling operations will be more efficient and economical if the individual areas for rolling are planned of sufficient length to reduce to a minimum the relative time required for turning. The Engineer on the job should be permitted to approve the stretches laid out for rolling to obtain as long a section as field conditions permit. Turn-around areas at the ends of the rolling section should be wide and satisfactorily prepared to

1. The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that proper record-keeping is essential for the transparency and accountability of the organization. This section also outlines the various methods used to collect and analyze data, ensuring that the information is reliable and up-to-date.

2. The second part of the document focuses on the implementation of the proposed changes. It details the steps involved in the rollout process, from initial planning to final execution. This section also addresses potential challenges and provides strategies to overcome them, ensuring a smooth transition to the new system.

3. The third part of the document discusses the ongoing monitoring and evaluation of the project. It highlights the need for continuous communication and collaboration between all stakeholders involved. This section also provides a timeline for the project, with key milestones and deadlines clearly defined.

4. The fourth part of the document concludes with a summary of the findings and recommendations. It reiterates the importance of the project and the need for continued support and resources. This section also provides a final overview of the project's goals and objectives, ensuring that all parties are aligned and committed to the success of the initiative.

reduce the time for turning around.

7. The approach fill at the intersection of Bevier Street, in the vicinity of Station 96, will be approximately 18 feet high. The weight of this fill on the foundation may be considerably greater than any pre-consolidation effect we might realize from the rolling operations, and it is expected that further settlement will be obtained in the foundation during and after construction. The amount of this settlement cannot be estimated, but will be a function of the age and type of material found in that foundation. It is recommended that this fill be built first to permit sufficient time for natural settlement and adjustment of the foundation under the superimposed load. The foundation should be first rolled in the same manner as the rest of it, planning to increase the amount of rolling with the 50-ton roller to 40 or more passes.
8. Our attention has been called to the existence of a storm water sewer line along the left side of the arterial route section. If this storm sewer line is within 8 feet of the surface, and within the section to be rolled in any area, precaution should be taken so that the heavy rolling will not damage the line.

9. Wherever local conditions permit, it is recommended that grade elevation be established a minimum of four feet above present ground line.
10. In cut sections, it is recommended that the area be excavated to one foot below subgrade level before the foundation rolling is started.
11. Based on an anticipated average area settlement of 2 feet due to the foundation rolling, approximately 40,000 cubic yards of common borrow should be added to the quantities, to compensate for the settlement and the fill to be added below present ground level between Stations 51 $\frac{1}{2}$ and 96 $\frac{1}{2}$.
12. Because of the possible future settlement that may develop, it is recommended that the pavement through this portion of the project be designed as a flexible pavement.
13. The quantities and costs covered in this report are for estimating purposes for the section of the project between Stations 51 $\frac{1}{2}$ and 96 $\frac{1}{2}$. These should be reviewed by the District when incorporated in the total job quantities.

1877

1877
1877
1877
1877

1877
1877
1877
1877

1877
1877
1877
1877

RECOMMENDED TENTATIVE SPECIFICATIONSITEM SPECIAL EMBANKMENT FOUNDATION ROLLING

(a) Work:-Under this Item the Contractor shall roll the embankment foundation with an approved pneumatic tired roller as directed by the Engineer.

Approved pneumatic tired equipment for rolling shall be of such capacity that the load may be varied from 30 to 50 tons. This load must be transmitted through two axles acting in a line perpendicular to the centerline of the roller to permit oscillating action. The total axle load shall be transmitted to the ground on four pneumatic tires. The pneumatic tires shall be evenly spaced across the entire width of the roller, and shall be attached two to each axle. The axles shall be so attached to the body of the roller that oscillation will be obtained in each set of two tires.

The rolling shall cover the entire foundation area between the toes of slope, from Station 51 $\frac{1}{2}$ to Station 96 $\frac{1}{2}$. These stations are approximate and may be varied in the field depending on local conditions. Preliminary rolling shall be done with a 30-ton axle load. It is expected that the amount of preliminary rolling required will be approximately 8 passes over the entire area.

THE UNIVERSITY OF CHICAGO

THE DIVISION OF THE PHYSICAL SCIENCES

DEPARTMENT OF CHEMISTRY

RECEIVED

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

1961

The axle load shall then be increased to a total load of 50 tons. Final rolling shall be done with the 50-ton axle load. This rolling shall be continued until the degree of stability of the foundation as required by the Engineer has been obtained. It is expected that the amount of rolling required with the roller loaded to a total weight of 50 tons will be approximately 25 to 30 passes over the entire area to be covered.

In rolling, one pass shall be taken to represent two trips of the roller, each trip offset from the other the width of one tire to obtain complete area coverage.

As the rolling progresses, the irregularities between tire marks shall be leveled off to facilitate compaction and to permit complete area coverage by the tires. All local depressions which interfere with the rolling operations shall be backfilled with Selected Borrow - Item 2EC.

The amount of backfill to be used for these operations shall be kept to the minimum required to permit easier rolling operations. When the condition of the foundation is satisfactory for normal rolling, the speed of the roller shall be not less than 2-1/2 miles per hour.

1. The first part of the paper is devoted to a discussion of the

main results of the theory of the

generalized functions of the

second order of the theory of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

generalized functions of the

(b) Payment:-The quantity to be paid for under this Item shall be the number of hours of rolling performed by the special rolling equipment. No payment will be made for idle equipment due to repairs, bad weather, wet subgrade, or for any other reason.

The time of rolling shall be recorded to the nearest minute by the Contractor. This time shall be checked daily by the Engineer.

The unit price bid for this Item shall include the cost of furnishing all labor, materials, fuel, equipment, and repairs necessary to complete the work, except the Selected Borrow used during these rolling operations will be paid for under its respective Item.

10

ACKNOWLEDGMENTS

This investigation was carried on under the general supervision of Mr. F.W. Donovan, District Engineer of District No. 9, Binghamton, New York. The field work was conducted under the direct supervision of Mr. L.W. Swank, formerly Assistant Soils Engineer and now Senior Civil Engineer of District No. 9, Binghamton, New York. Mr. P.H. Bird, Senior Engineering Geologist of the Bureau of Soil Mechanics, Albany, New York, was responsible for the Electrical Resistivity work made during this investigation. Mr. M.N. Sinacori, Associated Soils Engineer, Bureau of Soil Mechanics, Albany, New York, was in charge of the planning and coordination of the work, analysed the data, and prepared this report.

The Department wishes to express sincere appreciation to the William Bros Boiler and Manufacturing Company who offered the use of their 50-ton roller, to the Bero Engineering and Construction Company of Buffalo, New York, for the use of one of their D-7 Caterpillar Tractors, and to the McDougall Equipment Company of Binghamton, New York, for the use of their HD-19 Allis-Chalmers Tractor. This investigation was made possible by the cooperation of these organizations.

THE HISTORY OF THE
CITY OF BOSTON

FROM THE FIRST SETTLEMENT
TO THE PRESENT TIME
BY
JOSEPH NEALE, ESQ.
OF THE BARR

LONDON:
PRINTED BY J. JOHNSON, ST. PAUL'S CHURCH-YARD,
1796.

IN TWO VOLUMES.
VOL. I.

BOSTON:
PRINTED BY J. JOHNSON, ST. PAUL'S CHURCH-YARD,
1796.

THE HISTORY OF THE
CITY OF BOSTON

APPENDIX A



Fig. A-1 Rear View of roller showing tire spacing.



Fig. A-2 Roller loaded to 31 tons being pulled out of soft spot in turn-around area at end of Test Strip No. 2.

(

(


(



Fig. A-3 Test Strip No. 1 during rolling with 31-ton roller, showing irregularity of foundation under loose conditions. Surface material wet after rain.



Fig. A-4 Test Strip No. 2 following rolling with 50-ton roller, showing several weak spots.







Fig. A-5 Close-up of well-compacted stable surface during rolling with 50-ton roller. Test Strip No. 5.



Fig. A-6 Cracked surface of loose fill following several passes of 50-ton roller on natural ground. Test Strip No. 6.



1917



1917



Fig. A-7 Bad depression in turn-around area south of Test Strip No. 3, during rolling with 50-ton roller.



Fig. A-8 Weak foundation in Test Strip No. 7 bogging down 50-ton roller during first pass. No prior rolling given.








Fig. A-9 View of Test Strip No. 7 before rolling. Test Strip No. 1 seen on right.



Fig. A-10 View of Test Strip No. 7 after 5 passes with 50-ton roller. No other rolling given.





STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

PLAN OF TEST SECTIONS
AND BASE LINE PROFILE
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED NOV. 1, 1949



George W. McAlpin
GEORGE W. MCALPIN
PRIN. SOILS ENGINEER

DISTRICT NO. 9

COUNTY BROOME

DRAWING NO. 9SM 862






STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

PLAN OF TEST SECTIONS
AND BASE LINE PROFILE
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED NOV. 1, 1949
George W. McAlpin
PRIN. SOILS ENGINEER

DISTRICT NO. 9
COUNTY BROOME
DRAWING NO. 9SM 862




STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
GENERALIZED SOIL PROFILE	
FOR BASE LINE STA. 50+00 TO 97+00	
BRANDYWINE ARTERIAL (ROUTE 7)	
BINGHAMTON, N.Y.	
APPROVED Nov 23 1949	DISTRICT NO. 9
Seamus M. Alpin	COUNTY ENGINEER
DRAWING NO. 9 SM 871	

Soil Classification

P.D.H. = Preliminary

D.H. = Exploratory

APPENDIX B




SCALE - 1" = 30'

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

PLAN OF TYPICAL TEST STRIP
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON N.Y.

APPROVED Nov 23, 1949 DISTRICT NO. 9
COUNTY BROOME
PRINCIPAL SOILS ENGINEER
DRAWING NO. 9 SW 872



Sta.

84+50 ---

84+75 ---

85+25 --- x ---

85+75 ---

86+25 ---

86+50 ---

AVERAGE SETTLEMENT
vs. ROLLER PASSES
TEST SITE No. 1
STA. 84+50 to 86+50

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION COMPACTION RESULTS
FRANCY WINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED


19

DISTRICT NO. 2
COUNTY BEAUME

PRINCIPAL SOILS ENGINEER

DRAWING NO. 994873

FIG. B-2




Sta.
 84+50 ----
 84+75 ----
 85+25 ----
 85+75 ----
 86+25 ----
 86+50 ----

AVERAGE SETTLEMENT
 vs. ROLLER PASSES
 TEST STRIP No. 1
 STA. 84+50 to 86+50

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS	
FRANCYNE ARTERIAL (ROUTE 7)	
BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9
PRINCIPAL SOILS ENGINEER	COUNTY OF SCHUYLER
	DRAWING NO. 9 SM 873

Settlement (in)




Sta.	
80+50	—X—
80+75	— — —
81+25	— — — —
81+75	— — — —
82+25	— — — —
82+50	— — — —

AVERAGE SETTLEMENT
12 TON ROLLER PASSES
TEST STRIP No. 2
STA. 80+50 TO 82+50

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONFECTION RESULTS	
BRANDWINE ARTERIAL (ROUTE 7)	
BRANDWINE, N.Y.	
APPROVED	18 DISTRICT NO. 9
	COUNTY BRANDWINE
ENGINEER	1919

FIG. B-3



Sta.

80+50
80+75
81+25
81+75
82+25
82+50

— x —
— — —
— — —
— — —
— — —
— — —

AVERAGE SETTLEMENT
12 TON ROLLER PASSES
TEST STRIP NO. 2
STA. 80+50 TO 82+50


STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION CONFECTION RESULTS
BRANDWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED: [Signature]
COUNTY ENGINEER
DRAWN BY: [Signature] 11873

FIG. B-4

Settlement (Fe.)



12 Top Roller



Station	Roller Passes
73+00	—
73+25	— x —
73+75	— x —
74+25	— x —
74+75	— x —
75+00	—

AVERAGE SETTLEMENT
 15 ROLLER PASSES
 TEST STRIP No. 3
 STA. 73+00 to 75+00

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONSTRUCTION RESULTS	
BRANDYNE ARTERIAL (ROUTE 7)	
BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9
IN	COUNTY BROOME
PRINCIPAL SOIL ENGINEER	DRAWING NO. 9-15873

EUGENE LUTZGEN CO.
 MADE IN U.S.A.
 10 X 10 PER INCH

FIG. B-4



AVERAGE SETTLEMENT
15 ROLLER PASSES
TEST STRIP No. 3
STA. 73+00 to 75+00

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS


FOUNDATION COMACTION RESULTS
BRANDYVINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED BY DISTRICT NO. 9
COUNTY BROOME
PRINCIPAL SOIL ENGINEER DRAWING NO. 9-3M872

EUGENE DIEZGEN CO.
MADE IN U.S.A.
10 X 10 PER INCH

ENGINEERING PAPER CO.
MADE IN U.S.A.
10 X 10 PER INCH

Settlement (in)



Sta.	
63+00	—
63+25	—
63+75	—
64+25	—
64+75	—
65+00	— x —

AVERAGE SETTLEMENT
12 ROLLER PASSES
TEST SITE NO. 4
STA. 63+00 TO 65+00


STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION COMPACTNESS RESULTS
BRANDYHINE ARTERIAL (RAVINE)
BINGHAMTON, N.Y.

APPROVED: [Signature] DISTRICT NO. 9
COUNTY ENGINEER
DRAWN BY: [Signature] 7-2-87

EUGENE DREIZEN CO.
MADE IN U.S.A.


10 X 10 PER INCH



AVERAGE SETTLEMENT
VS. ROLLER PASSES
TEST SITE No. 4
STA. 63+00 VS. 65+00


Sta.
63+00
63+25
63+50
64+25
64+50
65+00


STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS BRANDYLINE ARTERIAL (RAIL) 1 BINGHAMTON, N.Y.	
APPROVED	DESIGN NO. 9
PRINCIPAL SOIL ENGINEER	COUNTY ENGINEER
	DRAWING NO. 7 BM873



Sta.
59+00
59+25
59+75
60+25
60+75
61+00

AVERAGE SETTLEMENT vs. ROLLER PASSES TEST STRIP NO. 5 STA. 59+00 To 61+00	
FOUNDATION COMPACTION RESULTS BRANDYWINE ARTERIAL (ROUTE 7) BIRCHINGTON, N.Y.	
9	BROOME
9	873





Sta.

63+00 ———
 63+25 ———
 63+75 ———
 64+25 ———
 64+75 — x —
 65+00 ———

AVERAGE SETTLEMENT
 13 ROLLER PASSES
 TEST STRIP No. 6
 STA. 63+00 to 65+00

FOUNDATION COMPACTON RESULTS


BRANDYWINE ARTERIAL (ROUTE 7)

ENG. JANTON, N.J.

9
 12

7 873





50 TON ROLLER


- 84+50
- 84+75
- 85+25
- 85+75
- 86+25
- 86+50

AVERAGE SETTLEMENT
VS. ROLLER PASSES
TEST STRIP NO. 7
STA. 84+50 TO 86+50

FOUNDATION COMPACTION RESULTS
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMTON, N.Y.

BROOME

FIG. B-8




KEUFFEL & ESSER CO., N. Y. NO. 3687-B13
10 X 10 to the Inch.
MADE IN U. S. A.

AVERAGE SETTLEMENT
VS. ROLLER PASSES
TEST STRIP NO. 7
STA. 84+50 TO 86+50

FOUNDATION COMPACTION RESULTS
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMTON, N. Y.

APPROVED: 9
BROOME
9-873


FIG. B-9



DEPARTMENT OF TRANSPORTATION
BUREAU OF PUBLIC ROADS
FOUNDATION COMPACTION RESULTS
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

9
E.C.F.W.E.
9 873

FIG. B-9



KEUFFEL & ESSER CO., N. Y. NO. 3897-9LG
10 X 10 to the Inch.
MADE IN U. S. A.

MAXIMUM AND
AVERAGE SETTLEMENT
vs. ROLLER PASSES
TEST STEP No. 2
STA. 80+75

STATE OF NEW YORK	
DEPARTMENT OF HIGHWAYS	
DIVISION OF SOILS	
BUREAU OF SOILS	
FOUNDATION COMPACTION RESULTS	
BRANDYWINE ARTERIAL (ROUTE 7)	
BINGHAMTON, N.Y.	
APPROVED	17 9
BY	EDDWE
DATE	9 7 53

Settlement (ft.)

0 5 10 55 60 65

1.0

2.0

3.0

4.0

5.0


tlement
4' L R


12 TON ROLLER

FOUNDATION COMPACTION RESULTS
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

BRIDGE

16 X 10 to the inch.
MADE IN U.S.A.





MAXIMUM AND
AVERAGE SETTLEMENT
vs ROLLER PASSES
TEST STRIP No. 6
STA. 64+25 & 65+00

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
OFFICE OF CONSTRUCTION
BUREAU OF HIGHWAYS
FOUNDATION COMPACTION RESULTS
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED


BY

DISTRICT NO. 9


COUNTY BROOME

DATE 9-18-73

FIG. 8-11





KEUFFEL & ESSER CO., N. Y. NO. 3457-3458
10 x 10 in. grid
MADE IN U.S.A.



SCALE - VERTICAL - 1" = 1/2'
HORIZONTAL - 1" = 2'

CROSS SECTION PROFILE
370.8475 TEST STRIP 1






STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS ARTERIAL ROUTE No. 7 BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9 COUNTY SCOTLAND DRAWING NO. 9 S M 072
10	PRINCIPAL SOILS ENGINEER

CROSS SECTION PROFILES
STA. 83+75 TEST STRIP #1


SCALE - VERTICAL = 1" = 10'
HORIZONTAL = 1" = 2'



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS	
ARTERIAL ROUTE No. 7	
BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9
19	COUNTY ACOMME
PRINCIPAL SOIL ENGINEER	DRAWING NO. 951874

CROSS SECTION PROFILES
57A 86+25 TEST STRIP 1

SCALE - VERTICAL - 1" = 1/2'
HORIZONTAL - 1" = 2'




CROSS SECTION PROFILE
574.86 ASD TEST STRIP


SCALE VERTICAL = 1" = 4' 0"
HORIZONTAL = 1" = 2'

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS	
ARTERIAL ROUTE No. 7	
SINGHARTON, NY	
APPROVED	DISTRICT NO. 9
	COUNTY SCHOENES
	DRAWING NO. 2587
PRINCIPAL SOIL ENGINEER	


FIG. 8-17




STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION DEPARTMENT RESULTS	
ARTERIAL ROUTE NO. 1	
ELMIRA, N.Y.	
APPROVED	DISTRICT NO. 9
PRINCIPAL SOILS ENGINEER	COUNTY OFFICE
	DRAWING NO. 95MBR




STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION INVESTIGATION RESULTS	
ARTERIAL ROUTE NO. 7	
BINGHAMTON, N.Y.	
APPROVED	19
DISTRICT NO. 9	COUNTY 5
DRAWING NO. 95M870	
PRINCIPAL SOIL ENGINEER	






STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FUNDING: CAPITALIZATION FUND	
APPROVAL DATE: 12/1/19	
APPROVAL NAME: A. W. HANCOCK, JR.	
APPROVED	DISTRICT NO. 9
19	COUNTY: RICHMOND
PRINCIPAL SOILS ENGINEER	DRAWING NO. 25876

FIG. 2-1




NO. 340-10 DIETZGEN GRAPH PAPER
10 X 10 PER INCH
EUGENE DIETZGEN CO.
MADE IN U. S. A.



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONSTRUCTION RESULTS	
ARTERIAL ROUTE NO. 1	
BROOKLYN	
APPROVED	DISTRICT NO. 9
19	COUNTY Brooklyn
DRAWING NO. 9 SM 872	
PRINCIPAL SOILS ENGINEER	

CROSS SECTION PROFILES
STA 82+50 TEST STRIP #2

SCALE - VERTICAL - 1" = 10'
HORIZONTAL - 1" = 10'



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION COMPARISON RESULTS
ARTIFICIAL ROAD NO. 7
ALBANY, N. Y.

APPROVED 19


DISTRICT NO. 9


COUNTY 56616

PRINCIPAL SOILS ENGINEER

DRAWING NO. 7 SM 876








STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONSTRUCTION RESULTS	
HUTCHINSON ROUTE No. 1	
BROOKLYN, N. Y.	
APPROVED	DISTRICT NO. 2
19	COUNTY BROOME
PRINCIPAL SOILS ENGINEER	DRAWING NO. 95M872

CROSS SECTION PROFILES
STA. 74+25 TEST STRIP #3


FIG. P-21



STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FUNDING INFORMATION REQUIRED ARTERIAL ROUTE NO. 17 CONTRACT NO. 19 COUNTY OF ALBANY DRAWING NO. 9 SM876	
APPROVED	PRINCIPAL SOILS ENGINEER

CROSS SECTION PROFILES
SIA 74475 TEST STRIP #3

SCALE - VERTICAL 1" = 4'
HORIZONTAL 1" = 10'



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION COMMISSION REPORT
ACCESSION NO. 1
JANUARY 1911

APPROVED: 19 DISTRICT NO. 9
COUNTY OF ALBANY
DRAWING NO. 95M878
NATURAL BUILDING ENGINEER

EDGE OF SECTION

SCALE - VERTICAL - $1'' = 1/2'$
HORIZONTAL - $1'' = 2'$

CROSS SECTION PROFILES
STA. 65+00 TEST STRIP #4

Addition

275

卷之四

卷之四

2144.51858

$$6-12/3000 + 12/64$$

1775

STATE OF NEW YORK

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION RESEARCH RESULTS

APR 21 1907

BINGHAMTON, N.Y.


APPROVED 19

DISTRICT NO. 9


[illegible]


COUNTY OF ...

DRAWING NO. 95



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION INFORMATION SHEET	
ARTERIAL ROUTE NO. 7	
ALBANY, N.Y.	
APPROVED	DISTRICT NO. 9
19	COUNTY SCHOENES
DRAWING NO. 95M876	
PRINCIPAL SOILS ENGINEER	





STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION CONSTRUCTION SECTION
ARTERIAL ROAD NO. 10
RUMFORDVILLE

APPROVED

10

DISTRICT NO. 9

COUNTY OF ALBANY


DRAWING NO. 2 SM 874


PRINCIPAL SOIL ENGINEER

20' x 5' SECTION PROFILES
STR. 63775 TEST STRIP #4


SCALE - VERTICAL - 1" = 10'
HORIZONTAL - 1" = 2'

FIG. B-33










STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOURTH DISTRICT	
ARTERIAL ROUTE NO. 7	
EIGHTH AVE.	
APPROVED	DISTRICT NO. 9
19	COUNTY RICHMOND
PRINCIPAL SOILS ENGINEER	DRAWING NO. 9 SM 876

CROSS SECTION PROFILES
STA. 60+75 TEST STRIPS


SCALE - VERTICAL - 1" = 1' 1/2"
HORIZONTAL - 1" = 2'



EDGE OF SECTION


STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
PROJECT: <i>ARTERIAL ROUTE 147</i>	
LOCATION: <i>ELIZABETH, N.J.</i>	
APPROVED	19
DISTRICT NO.	COUNTY
DRAWING NO. <i>2 SM 876</i>	


FIG. 1-1



STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FOUNDATION CLASSIFICATION RESULT GENERAL ROUTE NO. 7 EAST HEBBARD, N.Y.	
APPROVED	DISTRICT NO. 9 COUNTY: RICHMOND
PRINCIPAL SOILS ENGINEER DRAWING NO. 9 SM 876	

SCALE: VERTICAL: 1" = 12'
HORIZONTAL: 1" = 2'





EDGE OF SECTION


EDGE OF SECTION

STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF FIELD TECHNIQUES	
FUNDATION CORRELATION RESULTS	
ALLEGANY ROAD No. 7	
ELK HARBOR, N.Y.	
APPROVED	DISTRICT NO. 9
	COUNTY PROJECT
	DRAWING NO. 95886

CROSS SECTION PROFILES
STA. 37+00 TEST STRIP 2


SCALE - VERTICAL 1" = 4'
HORIZONTAL 1" = 12'

FIG. B-42



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONTRACT NO. 12345	
ARTERIAL ADDRESS NO. 123	
ENGINEER, N.Y.	
APPROVED	DISTRICT NO. 12
	COUNTY OF ALBANY
	DRAWING NO. 754876
PRINCIPAL, SOILS ENGINEER	

SCALE: VERTICAL 1" = 10'
HORIZONTAL 1" = 20'




STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
FOUNDATION CONSTRUCTION RESULTS	
ARTERIAL ROUTE No. 7	
FLAGSTAFF, N.Y.	
APPROVED	DISTRICT NO. 9
PRINCIPAL SOIL ENGINEER	COUNTY, FILLMORE
	DRAWING NO. 9 SW 876



STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS	
ARTERIAL ROUTE No. 7 BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9 COUNTY CATTARAUGUS
10	DRAWING NO. 95M876
PRINCIPAL SOILS ENGINEER	

7.5 #6



EDGE OF SECTION A

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

FOUNDATION CONNECTION DETAILS
GENERAL NOTE NO. 7
EUGENIA, NY

APPROVED


19


DISTRICT NO. 9
COUNTY, ALBANY

PRINCIPAL SOILS ENGINEER

DRAWING NO. 9 5M876

FIG. B-45






STATE OF NEW YORK DEPARTMENT OF PUBLIC WORKS DIVISION OF CONSTRUCTION BUREAU OF SOIL MECHANICS	
FOUNDATION COMPACTION RESULTS ARTERIAL ROUTE No. 7 BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9 COUNTY ENGINEER
19	DRAWING NO. 95MB76
PRINCIPAL SOILS ENGINEER	


SCALE: VERTICAL - 1" = 10'
HORIZONTAL - 1" = 2'

Settlement (in)



TEST STRIP #3

Settlement (in)




TEST STRIP #4


SETTLEMENT ALONG TEST STRIP #
VS. ROLLER PASSES
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

Nov 23 49

9
BROOME
9 875




APPENDIX C




Note: Electrode spacing equals
approx. depth at which
resistivity is measured.

Center, rolled 31
2' W of E edge rolled 31
1' E of E edge not rolled


STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
RESISTIVITY PUMP TEST STRAITS	
ELBA MINING AREA, ALLEGANY COUNTY, N.Y.	
BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 9
16	COUNTY ALLEGANY
DRAWING NO. 19 SM 876	





STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL INVESTIGATION	
RESISTIVITY POINT TEST, ST. 12, 14, 15	
BRANDYwine ARTERIAL (ROUTE 1)	
BINGHAMTON, N.Y.	
APPROVED	DISTRICT NO. 2
	COUNTY BROOME
	DRAWING NO. 9, 14, 15

Test No.	2	15	15	15	15	15
Spacing	2	15	15	15	15	15
Resistance	250	200	150	100	50	20




Note: Electrode spacing equals
approx. depth at which
resistivity is measured

Test No. 3	not rolled
" " 16	rolled @ 12'
" " 35	" " 31'
" " 44	" " 50'

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
RESISTIVITY POINT TEST STA 74100	
BRANDYVINE ARTERIAL ROUTE 11	
BINGHAMTON, N. Y.	
APPROVED	DISTRICT NO. 9
COUNTY BRIDGEMAN	
DRAWING NO. 9 SM 876	

FIG. C-4




STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF ROAD RECONSTRUCTION

RESISTIVITY POINT TEST STA 73+50
BRANDYwine ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED _____ DATED NO. 9
COUNTY BROOME
DRAWING NO. 9-1876


PRINCIPAL SURVEYOR



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS
BUREAU OF TRAILS

RESISTIVITY POINT TEST STA 13+00
BRADYHINE ARTERIAL LANE
BINGHAMTON, N.Y.

DISTRICT NO. 9
COUNTY BROOME
DRAWING NO. 9-1876



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

RESISTIVITY ADJUT TEST SIA 65500
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMPTON, N.Y.

APPROVED: 14 DISTRICT NO. 9
COUNTY BROOME
DRAWING NO. 95M876

Electrode Spacing (ft)

2 4 6 8 10 12 14 16 18 20

Note: Electrode spacing equals
approx. depth at which
resistivity is measured.

Approx. 2000 ohm/cm²

1500

Resistivity

1000

Approx. 500


Test 100 ft

" " 100 ft

Test 120 ft

" " 120 ft

STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
BUREAU OF HIGHWAY CONSTRUCTION	
RESISTIVITY PUMP TEST STA 64.450	
BERNDYRINE ARTERIAL (ROUTE 1)	
BINGHAMTON, N. Y.	
APPROVED	18
TEST NO. 9	19
COUNTY	ESSEX
DRAWING NO.	9-5886



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

RESISTIVITY POINT TEST (NO. 21)
BRENDYME MATERIAL (NO. 17)
BINGHAMTON, N. Y.

APPROVED: _____
DIRECTOR NO. 9
CHURCHY BROOME
DRAWING NO. 9-54876






FIG. C-11

APPARENT RESISTIVITY

2100

1800

1500

1200

900

63+00

+20

+40

ELECTRODE SPACING = 5' APPROX.
DEPTH RESISTIVITY IS MEASURED.


FORE ROLLING

AVERAGE
VALUES

12 PASSES 17 TON
12 PASSES 31 TON
38 1/2 PASSES 50 TON


DEPARTMENT OF HIGHWAYS
BUREAU OF PUBLIC WORKS
ELECTRIC RESISTIVITY TRAVERSE
STR. 63+00 TO 65+00
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMTON, N.Y.
9
BROOME
9 54 377

NOTE: ELECTRODE SPACING = 5' APPROX.
DEPTH RESISTIVITY IS MEASURED.



DEPARTMENT OF HIGHWAYS	
ELECTRIC RESISTIVITY TRAVERSE	
STA. 63+00 TO 65+00	
BRANDYWINE ARTERIAL (ROUTE 1)	
BINGHAMTON, N.Y.	
DATE	9
BY	BROOME
CHECKED BY	9 54377

APPARENT RESISTIVITY



NOTE: ELECTRODE SPACING = 10'
APPROX. DEPTH
RESISTIVITY IS MEASURED

AVERAGE
VALUES

RE ROLLING


12 PASSES 12 TON
12 PASSES 31 TON
35 PASSES 10 TON

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS


ELECTRIC RESISTIVITY TRAVERSE
STA. 63+00 TO 65+00
BRANDYwine ARTERIAL (ROUTE 1)
BINGHAMTON, N.Y.

APPROVED: J. B. ... 9
COUNTY BROOME
DATE: ... 9 + 877

FIG. C-13



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
DIVISION OF CONSTRUCTION	
BUREAU OF SOIL MECHANICS	
ELECTRIC RESISTIVITY TRAVERSE	
STA. 63+00 TO 65+00	
BRANDYHINE ARTERIAL (ROUTE 1)	
BINGHAMTON, N.Y.	
APPROVED	DESIGNED BY 9
	COUNTY BROOME
	DRAWING NO. 9-1877



ELECTRODE SPACING = 15' - APPROX.
DEPTH RESISTIVITY IS MEASURED

AVERAGE
VALUES

EE ROLLING

12 PASSES 12 TON
12 PASSES 31 TON
38% PASSES 50 TON


DEPARTMENT OF TRANSPORTATION

ELECTRIC RESISTIVITY TRAVERSE
STA. 63+00 TO 65+00
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N. Y.

APPROVED

BROOME


9-1-87



MADE IN U.S.A.

10 X 10 PER INCH

APPARENT RESISTANCE



ELECTRODE SPACING = 5' APPROX.
DEPTH RESISTANCE IS MEASURED.


LED 12 PASSES 12T,
12 PASSES 31T

AVERAGE
VALUES

ED ADDITIONAL
PASSES 30T

ELECTRIC RESISTIVITY TRAVERSE
STA. 73+00 TO 75+00
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N. Y.

9
BROOME
9-37T



DEPARTMENT OF TRANSPORTATION	STATE OF NEW YORK
ELECTRIC RESISTIVITY TRAVERSE	
STA. 73+00 TO 75+00	
BRANDYWINE ARTERIAL (ROUTE 7)	
BINGHAMTON, N. Y.	
DATE	9
BY	BROOME
CHECKED BY	9-3-81

APPARENT RESISTANCE

3000

2500

2000

1500

1000

500

0

75+00

75+25

75+50

ELECTRODE SPACING = 10' - APPROX.
DEPTH RESISTANCE IS MEASURED.

RE ROLLING

ED 12 PASSES 12T,
12 PASSES 31T

ED ADDITIONAL
PASSES 31TON

AVERAGE
VALUES

ELECTRIC RESISTIVITY TRAVERSE
STA. 73+00 TO 75+00

BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

COUNTY BROOME

9-877

FIG. C-16

NOTE: ELECTRODE SPACING = 10' - APPROX.
DEPTH RESISTANCE IS MEASURED.

APPARENT RESISTANCE

AVERAGE
VALUES

BEFORE ROLLING

ROLLED 12 PASSES 12T,
12 PASSES 31T

ROLLED ADDITIONAL
12 PASSES 30TON

STATION

DATE	10/15/51
BY	J. W. B. BROOME
ELECTRIC RESISTIVITY TRAVERSE	
STA. 73+00 TO 75+00	
BRANDYWINE ARTERIAL (ROUTE 7)	
BINGHAMTON, N.Y.	
BY	J. W. B. BROOME
DATE	9-1-57

EUGENE DIEZSEN CO.
MADE IN U.S.A.
10 X 10 PER INCH

ELECTRODE SPACING = 5' - APPROX.
 DEPTH RESISTIVITY IS MEASURED

AVERAGE
 VALUES

APPARENT RESISTIVITY

BEFORE ROLLING

12 PASSES 12 TON
 12 PASSES 31 TON

7 PASSES 12 TON
 7 PASSES 31 TON
 7 PASSES 50 TON

STATE OF NEW YORK
 DEPARTMENT OF PUBLIC WORKS

ELECTRIC RESISTIVITY TRAVERSE
 STA. B5+50 TO B6+50
 BRANDYWINE ARTERIAL (ROUTE 1)
 BINGHAMTON, N. Y.

APPROVED: [Signature]
 DATE: [Date]
 DRAWING NO. 95M871



STATE OF NEW YORK	
DEPARTMENT OF PUBLIC WORKS	
BUREAU OF HIGHWAYS	
ELECTRIC RESISTIVITY TRAVERSE	
STA. 85+50 TO 86+50	
BRANDYWINE ARTERIAL (ROUTE 1)	
BINGHAMTON, N. Y.	
APPROVED	DATE
DRAWN	BY
CHECKED	BY
DATE	BY

ELECTRODE SPACING = 11" = APPROX.
DEPTH RESISTIVITY IS MEASURED.

APPARENT RESISTIVITY

BEFORE ROLLING

AVERAGE
VALUES

12 PASSES 12 TON
12 PASSES 3 TON

12 PASSES 12 TON
12 PASSES 31 TON
38 1/2 PASSES 50 TON

ELECTRIC RESISTIVITY TRAVERSE
STA. 85+50 TO 86+50
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMTON, N.Y.

NOTE: ELECTRODE SPACING = 10' APPROX.
DEPTH RESISTIVITY IS MEASURED.

APPARENT RESISTIVITY

BEFORE ROLLING

AVERAGE
VALUES

12 PASSES 12 TON
12 PASSES 31 TON

12 PASSES 12 TON
12 PASSES 31 TON
38 1/2 PASSES 50 TON

STATION


ELECTRIC RESISTIVITY TRAVERSE
STA. 85+50 TO 86+50
BRANDYWINE ARTERIAL (ROUTE 1)
BINGHAMTON, N.Y.

BROOME
9-877

EUGENE W. PETERSON CO.
MADE IN U.S.A.

10 X 10 PER INCH

APPENDIX D



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

RESISTANCE TO PENETRATION VS. DEPTH
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N. Y.


APPROVED

DISTRICT NO. 9

COUNTY BROOME

PRINCIPAL SOIL ENGINEER

FILE NO. 96-578





EUGENE DIETZEN CO.
MADE IN U. S. A.
10 X 10 PER INCH
GRAPH PAPER

STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

RESISTANCE TO PENETRATION VS. DEPTH
BRANDWINE ARTERIAL (ROUTE 7)
BINGHAMTON, NY.

APPROVED: _____
DISTRICT NO. 9
COUNTY BROOME
BRANDWINE DISTRICT






STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF HIGHWAYS
BUREAU OF TRAFFIC ENGINEERING

RESUME OF PENETRATION VS. DEPTH

BRANCH LINE ARTERIAL (ROUTE 71)
BINGHAMTON, N.Y.

APPROVED: 13 DISTRICT NO. 9
COUNTY OF SCHOENEBROOK
DATE: 9-2-87



STATE OF NEW YORK
DEPARTMENT OF PUBLIC WORKS
DIVISION OF CONSTRUCTION
BUREAU OF SOIL MECHANICS

RESISTANCE TO PENETRATION VS. DEPTH
BRANDYWINE ARTERIAL (ROUTE 7)
BINGHAMTON, N.Y.

APPROVED

IN

RECORD NO. 9

COUNTY BROOME

PRINCIPAL ENGINEER

DRAWING NO. 95M87B

TABULATED PENETRATION TEST DATA

TEST STRIP NO. 2

AT STATIONS SHOWN

Depth (ft.)	80+75	81+00	81+25	81+50	81+75	82+00	82+25	82+50
	A B	A B	A B	A B	A B	A B	A B	A B
1	17	10	15	5	5	5	7	20
2	13	9	9	7	3	10	6	13
3	4	5	8	2	2	4	7	7
4	3	4	3	1	1	2	3	7
5	2	2	3	1	1	3	2	4
6	3	15	15	5	8	15	7	9
7	5	10	13	9	4	17	6	10
8	7	7	7	8	3	9	8	9
9	7	11	6	9	3	7	9	6
10	10	12	4	12	5	5	13	2
11	7	10	4	12	20	11	10	2
12	11	11	7	8	20	10	10	3
13	9	9	9	9	36	4	9	3
14	9	7	10	10	23	3	5	16
15	12	15	15	6	2	4	4	24
16	11	12	13	3	150	9	3	5
17	9	10	9	7	110	15	2	6
18	7	16	10	5	7	15	8	6
19	7	12	7	1	9	9	3	5
20	7	12	7	10	9	13	5	10

A = Blows per foot on probing rod, Station points 25 feet of Base line, area not rolled.

B = Blows per foot on probing rod, Station points 10 feet of Base Line, area completely rolled.

TABULATED PENETRATION TEST DATA
TEST STRIP NO. 3
AT STATIONS SHOWN

Depth (ft.)	73+50	73+75	74+00	74+25	74+50	74+75	75+00
	A B	A B	A B	A B	A B	A B	A B
1	18	25	23	10	8	13	18
2	10	33	20	14	33	13	4
3	8	14	10	5	6	13	5
4	12	7	13	16	6	12	5
5	11	7	11	8	9	12	10
6	14	11	15	7	8	17	12
7	21	18	18	14	21	15	24
8	15	10	21	30	10	34	7
9	17	8	9	12	13	20	10
10	20	7	9	15	19	20	6
11	15	17	14	29	80	59	9
12	24	24	10	16	27	20	14
13	10	11	11	16	19	16	14
14	6	11	13	10	21	69	9
15	9	8	29	8	26	33	7
16	9	8	7	13	6	7	13
17	18	10	10	11	8	10	13
18	16	8	13	9	20	26	12
19	16	13	7	8	16	27	12
20	15	12	10	5	5	19	10
	12	13	4	5	6	17	8

A = Blows per foot on probing rod, Station points 15 feet left of Base line, area not rolled.
 B = Blows per foot on probing rod, Station points 3 feet right of Base line, area completely rolled.

TABULATED PENETRATION TEST DATA

TEST STRIP NO. 4

AT STATIONS SHOWN

Depth (ft.)	63/25		63/50		63/75		64/00		64/25		64/75	
	A	B	A	B	A	B	A	B	A	B	A	B
1	10	27	11	19	19	7	13	5	16	11	10	22
2	14	36	30	50	16	24	15	15	16	19	40	45
3	1	13	15	30	10	17	20	19	16	29	11	47
4	1	18	10	15	12	15	12	24	10	31	12	13
5	1	19	13	12	31	25	18	40	15	24	14	21
6	3	8	20	7	7	29	12	21	7	20	31	19
7	2	6	5	11	11	15	6	9	9	21	34	13
8	3	5	5	7	13	12	5	12	9	23	10	12
9	3	5	4	9	16	8	4	10	15	10	18	10
10	3	7	3	6	9	7	4	8	7	9	12	10
11	8	11	7	13	13	14	11	16	12	15	10	16
12	8	11	11	11	14	9	13	14	11	15	13	14
13	7	12	6	11	11	15	10	21	17	22	11	14
14	6	8	6	9	10	12	18	27	19	25	12	12
15	15	10	4	10	20	10	20	17	18	20	12	13
16	25	10	15	15	22	19	27	20	20	17	24	19
17	54	16	45	10	48	25	32	19	22	20	27	22
18	49	14	13	7	41	28	28	19	11	24	30	26
19	31	16	19	9	15	29	12	20	29	25	37	19
20	16	22	12	19	13	27	16	31	28	25	54	22

A= Blows per foot on probing rod, Station points 15 feet left of Base Line, area not rolled.
 B= Blows per foot on probing rod, Station points 4 feet right of Base Line, area completely rolled.

TABULATED PENETRATION TEST DATA

TEST STRIP NO. 5

AT STATIONS SHOWN

Depth (ft.)	59+25 A	59+25 B	59+50 A	59+50 B	59+75 A	59+75 B	60+00 A	60+00 B	60+25 A	60+25 B	60+50 A	60+50 B	60+75 A	60+75 B
1	20	40	32	52	39	41	32	37	47	52	32	63	35	37
2	27	38	23	47	25	49	59	52	38	40	49	31	30	65
3	24	39	10	20	22	20	9	19	39	23	29	19	24	15
4	12	22	8	25	8	17	5	17	9	19	10	9	19	21
5	13	52	4	19	5	26	4	23	12	15	19	11	17	15
6	4	27	3	17	17	15	4	25	10	14	8	6	5	12
7	6	29	4	18	13	20	11	18	4	11	6	16	4	4
8	6	30	7	19	2	18	7	19	7	11	3	11	6	7
9	8	35	3	30	3	15	9	10	11	17	12	16	8	8
10	13	20	10	37	6	17	15	10	15	8	12	19	10	10
11	17	18	16	25	9	17	20	12	16	8	15	9	15	11
12	14	17	10	10	8	9	18	11	11	21	17	8	14	12
13	10	10	10	16	7	11	16	9	16	19	17	6	14	16
14	10	30	10	19	7	11	23	25	11	11	29	9	16	27
15	13	27	17	24	12	27	43	20	29	31	22	45	20	36
16	6	31	33	30	29	25	57	19	70	28	31	32	35	38
17	38	42	48	31	30	30	49	31	73	26	29	37	37	30
18	35	30	40	39	39	39	49	43	54	30	25	23	37	28
19	29	30	39	29	27	39	38	44	30	30	36	26	30	20
20	25	29	29	30	23	39	40	31	23	30	20	28	31	30

A = Blows per foot on probing rod, Station points 15 feet left of Base line, area not rolled.

B = Blows per foot on probing rod, Station points 3 feet right of Base line, area completely rolled.

N.Y.S. - D.P.W. - B of S. M.
AUTHOR
Foundation Rolling Rt. #7
TITLE
Brandywine Arterial Ext.
DATE LOANED BORROWER'S NAME DATE RETURNED
Bingha

ACCOPRESS BINDER

BF 250

Made By
ACCO PRODUCTS, INC.
Ogdensburg, N. Y., U.S.A.

00364



LRI